


Do not scale this drawing (printed or electronic version).
 Contractors must check all dimensions from site.
 This drawing is copyright and is for use on this site only. This drawing should be read in conjunction with all relevant consultants drawings and specialist subcontractors / supply chain drawings and specifications.
 All works to be carried out in accordance with the latest British Standards / Codes of Practice unless specifically directed otherwise in the specification.
 Responsibility for the reproduction of this drawing in paper form, or issued in electronic format, lies with the recipient to check that all information has been replicated in full and is correct when compared to the original paper or electronic image.
 Graphical representations of equipment on this drawing have been co-ordinated, but are approximations only. Please refer to the specifications and / or details for actual sizes and / or specific contractor construction information.



KEY

Hard Landscape

- Bitmac - Vehicular surface [Total Area - 4,865.0m²]
- Bitmac - Pedestrian surface [Total Area - 1119m²]
- Self landing gravel [Total Area - 3,477.1m²]
- Flag paving [Total Area - 1,001.8m²]
- Permeable block paving [Total Area - 692.2m²]
- Grass concrete [Total Area - 1,277.2m²]
- Geogrid paving system www.abp-geosynthetics.com/products/subspave.html [Total Area - 100.4m²]
- PCC Road Kerb incl. Dropped kerbs, angles, and transition pieces [Total Length - 2,076m]
- Handrails - DDA Compliant
- Retaining Wall - Stone filled gabion Baskets (Specification to match engineer/architectural elements)

Soft Landscape

- Proposed earthwork contours
- Street tree planting: Heavy standard 12-14cm girth [Total - 103 No.]
- Informal native tree planting: Select standard 10-12cm girth [Total - 147 No.]
- Amenity grass seed
- Proposed ornamental flowering herbaceous planting: To car park and arrival spaces [Total area - 784.2m²]
- Proposed ornamental ground cover planting: To car park and arrival spaces [Total area - 440.2m²]
- Proposed ornamental shrub planting: To car park and arrival spaces [Total area - 903.4m²]
- Proposed native shrub planting: To site boundary & arrival spaces [Total area - 2,221.5m²]
- Proposed native hedge planting [Total area - 313.4 linear m]
- Proposed pollen & nectar wildflower mix
- Proposed native woodland planting mix: White & leathers [Total area - 4,334m²]
- Proposed semi aquatic / marginal planting: To pond and SUDs areas
- Proposed semi aquatic / marginal planting: To pond and SUDs areas
- Proposed pitch surfacing: Specification by specialist [Total area - 31,745m²]
- Existing hedgrows and trees to be retained
- Existing hedgrows and trees to be retained
- Existing hedge planting: To be improved and infilled where required
- Existing hedgrows to be transplanted [Total area - 1689m²]
- Proposed wet meadow mix in formed ditches [Total length - 500m]
- Proposed species rich grassland

REV.	DATE	DESCRIPTION	DRAWN	CHK'D
P32	22/12/22	AMENDED ISSUE	SA	ME
P31	20/12/22	AMENDED ISSUE	SA	ME
P30	19/12/22	AMENDED ISSUE	SA	ME
P28	08/12/22	AMENDED ISSUE	SA	ME
P27	25/11/22	AMENDED ISSUE	SA	ME
P26	24/11/22	AMENDED ISSUE	SA	ME
P25	21/11/22	AMENDED ISSUE	KT	SA
P24	17/11/22	AMENDED ACCESS ROAD	SA	ME



A: Ground Floor, The Tower,
 Deva City Office Park, Trinity Way,
 Manchester M3 7BF
 T: +44 (0) 161 312 3131
weareurbangreen.co.uk

Client: **ERIC WRIGHT**

Project: **CRICKET FACILITY, FARINGTON**

Title: **GENERAL ARRANGEMENT**

Issue: **PLANNING**

Drawn: RS	Checked: SA	Approved: MT
Project: UG1016	Scale @ A1: 1:1000	Date: 09/08/21
Dwg No: UG_1016_LAN_GA_DRW_01	Revision: P32	